

Tower: Six (6) Tower Cells

Scope of Services

Fill Replacement

- Provide all Supervision. Labor, Tools and Rental Equipment to remove the existing deteriorating fill media and supports from three (3) two (2) cell cooling towers.
- All waste material will be placed into dumpsters..
- Provide all Supervision, Labor, Tools, Material, and Freight to install new PVC fill kit to include:
 - PVC Film Fill Media 15 mil
 - PVC Drift Eliminators
 - Fiberglass and Stainless Steel Support System
 - All required assembly fasteners and sealants

Cost to complete all six (6) tower cells is given in the following breakout pricing:

Materials & Freight:

Labor:

Dumpsters/Rental Equipment:

Total Cost: